


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 2 Twp. 16 Rge. 12 (E) (W) x
Location as "NE/CNW%SW%" or footage from lines SW NE SW
Lease Owner Herman George Kaiser
Lease Name Schenf "B" Well No. #1
Office Address 909 Palace Bldg. Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-12-69 _____ 19____
Plugging completed 9-15-69 _____ 19____
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3347' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3340'	2851.96'
				8 5/8"	313'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3320'. Mixed and ran 5 sacks cement thru dump bailer.
Squeezed hole with 15 sacks gel and displaced with 15 sacks pozmix with 2% gel added.

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16 day of September, 19 69

My commission expires _____



Sidney D. Miller
Notary Public.

DRILLER'S LOG

COMPANY: Herman George Kaiser
 Oil Producer
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SCHAUF B-#1
 LOCATION: SW NE SW Sec. 2-16S-12W
 BARTON COUNTY, KANSAS
 COMMENCED: 11-22-63
 COMPLETED: 11-28-63

0 10
 10 100
 100 320
 320 340
 340 755
 755 785
 785 1115
 1115 1610
 1610 1875
 1875 2045
 2045 2150
 2150 2310
 2310 2515
 2515 2715
 2715 2924
 2924 3045
 3045 3347
3347

Surface Soil
 Limestone
 Shale & Shells
 Shale
 Shale & Shells
 Anhydrite
 Redbed & Shale
 Shale & Lime
 Lime
 Lime & Shale
 Shale & Lime
 Shale
 Shale & Lime
 Lime & Shale
 Lime
 Shale & Lime Streaks
 Lime (Arbuckle Top @ 3340)
Rotary Total Depth - Set 5 1/2"
 Casing

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 22 1969
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 320' with landing joint Cemented with 175 sacks Sunset.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schauf B-#1, located SW NE SW of Section 2, Township 16 South, Range 12 West, Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 29th day of November, 1963.

Ulanda Nichols
 Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1967