

API NUMBER 185 22 494 - 6000

LEASE NAME Zimmerman

WELL NUMBER 1

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 28 TWP. 23 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 12/1/24/87

Plugging Commenced 12/1/24/87

Plugging Completed 12/1/24/87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 410 One Main Place

PHONE# 916-262-3596 OPERATORS LICENSE NO. 09408

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Paul Luthl (KCC District Agent's Name).

Is ACC-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3961

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

FEB 17 1988 2-12-88

per attached CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Trans Pac Drilling, Inc. License No. 05841

Address 410 One Main Place Wichita, ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Pugh (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary Pugh

(Address) Rt 1 Seward, ks. 67577



SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 88

Sondra J. Felcia  
 Notary Public

My Commission Expires: May 13, 1991

DRILLERS WELL LOG

DATE COMMENCED: October 12, 1987  
DATE COMPLETED: October 19, 1987

Davis Petroleum, Inc.  
Zimmerman #1  
SW SW NE  
Sec. 28, T23S, R13W  
Stafford County, KS

ELEVATION: 1897 K.B.

0 - 772' Surface Soil, Sand, Red Bed  
772 - 810' Anhydrite  
810 - 3337' Shale, Lime  
3337 - 3342' Shale  
3342 - 3503' Lime, Shale  
3503 - 3758' Lime  
3758 - 3912' Shale, Lime, Chert  
3912 - 3950' Shale, Lime  
3950 - 3955' Dolomite  
3955' RTD

FORMATION DATA	
Anhydrite	772-810'
Heebner	3337
Toronto	3362
Douglas	3377
Br. Lime	3478
Kansas City	3503
Base K.C.	3758
Mississippi	3816
Viola	3848
Simpson	3912
Arbuckle	3950
RTD	3955

Surface Pipe: Set new 8-5/8" pipe, 20# at 302' with 175 sacks 60/40 pozmix, 2% gel, 3% c.c.


A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

LEONARD WILLIAMSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*  
Leonard Williamson

SUBSCRIBED AND SWORN to before me this 21st day of October, 1987.



*Dorothy M. Hague*  
Notary Public

RECEIVED  
STATE CORPORATIONS COMMISSION

OCT 23 1987

CONSERVATION DIVISION  
Wichita, Kansas