

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,433-0000

LEASE NAME O'Connor

WELL NUMBER 2-28

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 28 TWP. 23 RGE. 13 ~~NE~~ or (W)

COUNTY Stafford

Date Well Completed 5-21-87

Plugging Commenced 5-21-87

Plugging Completed 5-21-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rine Exploration Company

ADDRESS #654 300 W. Douglas Wichita, KS 67202

PHONE#(316) 262-5418 OPERATORS LICENSE NO. 5020

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City
to be filed by _____

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4007

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 800' w/50 sacks cement thru drill pipe

Next Plug: @ 430' w/40 " " " " "

Next Plug: @ 40' w/10 sacks " " " " "

15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 26 day of May, 1987



RECEIVED
STATE CORPORATION COMMISSION
Expires: 5-5-90

Dorothy M Hague
Notary Public

MAY 27 1987

Recd
5-27-87

CONSERVATION DIVISION
Wichita, Kansas

15-195-22433-0000

DRILLER'S WELL LOG

DATE COMMENCED: May 11, 1987
DATE COMPLETED: May 21, 1987

Pine Exploration Company
O'CONNOR #2-28
C NE 37
Sec. 20, T23S, R13W
Stafford County, Ks.

ELEVATION: 1897 K.B.

0	-	777'	Surface Soil, Sand, Shale, Red Bed
777	-	802'	Anhydrite
802	-	3344'	Shale & Lime
3344	-	3348'	Shale
3348	-	3508'	Lime & Shale
3508	-	3760'	Lime
3760	-	3817'	Shale & Lime
3817	-	3843'	Chert & Lime
3843	-	3920'	Chert
3920	-	3959'	Sand
3959	-	4007'	Dolomite
		4007'	RTD

FORMATION DATA

Anhydrite	777'
Hebner	3344'
Br. Lime	3484'
Lansing	3508'
Page K.C.	3760'
Mississippi	3817'
Viola	3848'
Simpson	3920'
Arbuckle	3959'
RTD	4007'

Surface Pipe: Set new
3-5/8" 24# pipe @402'
w/225 sacks 60/40 pozmix
2% gel 38 cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ss.

Leonard Williamson of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this _____ day of May 1987.

 DOROTHY M. HAGUE
NOTARY PUBLIC
STATE OF KANSAS
My Appl. Exp. 5-5-90

Dorothy M. Hague
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 1987

CONSERVATION DIVISION
Wichita, Kansas