

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,359-0000

LEASE NAME O'Connor

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-28

990 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 28 TWP. 23 RGE. 13 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Rine Exploration Company

ADDRESS Suite #645, 300 W. Douglas, Wichita, KS 67202

PHONE#(316) 262-5418 OPERATORS LICENSE NO. 5020

Date Well Completed 3-15-86

Character of Well D&A

Plugging Commenced 3-15-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-15-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.
to be filed by _____

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4040'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 3984' w/40 sacks cement thru drill pipe

Next Plug: @ 805' w/50 " " " " "

Next Plug: @ 410' w/40 " " " " "

Next Plug: @ 40' w/1 sack Hulls & 10 sacks cement 15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or (~~XXXXXX~~) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 17 day of March, 1986

Dorothy M. Laque
Notary Public

My Commission Expires: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1986 3-19-86

CONSERVATION DIVISION

15-185-22359-0000

DRILLER'S WELL LOG

DATE COMMENCED: March 8, 1986
DATE COMPLETED: March 15, 1986

Rine Exploration Company
O'CONNOR #1-28
N/2 SW SW
Sec. 28, T23S, R13W
Stafford County, Ks.

ELEVATION: 1900 K..B.

0 - 781' Surface Soil, Snad, Shale
781 - 805' Anhydrite
805 - 3030' Shale & Lime
3030 - 3044' Shale & Sand
3044 - 3360' Lime
3360 - 3399' Shale & Lime
3399 - 3497' Shale
3497 - 3514' Lime & Shale
3514 - 3753' Lime
3753 - 3983' Shale, Lime, Chert, Sand
3983 - 4040' Dolomite
4040' RTD

FORMATION DATA

Anhydrite 781'
Severy 3030'
Topeka 3044'
Heebner 3360'
Toronto 3385'
Douglas 3399'
Br. Lime 3497'
Kansas City 3514'
Base K.C. 3753'
Conglomerate 3777'
Mississippi 3850'
Viola 3886'
Simson Sh. 3915'
Arbuckle 3883'
RTD 4040'

Surface Pipe: Set new 8-5/8",
23# pipe @379' w/200 sacks
60/40 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 17 day of March 1986.

My Comm. Expires:
4-29-86

Dorothy M. Hague
Notary Public

Wichita, Kansas

RECORDED
STATE CORPORATION COMMISSION
MAR 19 1986
CONSERVATION DIVISION
Wichita, Kansas