


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Stafford

County. Sec. 30 Twp. N23S Rge. (K) 13 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW SW

Lease Owner The Vickers Petroleum Co., Inc.

Lease Name Radke Well No. 1

Office Address 21 W-K-H Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 18 1944

Application for plugging filed August 18 1944

Application for plugging approved August 18 1944

Plugging commenced August 18 1944

Plugging completed August 19 1944

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 4032 Bottom 4075 Total Depth of Well 4075 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing-Kansas City	Dry	3564	3775	10 $\frac{3}{4}$	450	None
Base Kansas City	"	3775				
Conglomerate	"	3900				
Simpson Shale	"	3975				
Simpson Sand	"	3996				
Arbuckle	"	4032				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud total depth to 450', bridge + 15 sacks cement, mud to 25', bridge cement to 12', mud to surface.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Vickers Petroleum Co., Inc.

Address 201 W-K-H Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John M. Little

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

201 W-K-H Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 24th day of August 1944

My commission expires Oct. 24, 1944

Notary Public.

15-185-01326-0000

THE VICKERS PETROLEUM CO., INC.

Radke No. 1
NE SW SW Sec. 30, Twp. 23S, Rge. 13W
Stafford County, Kansas

Casing Record:
10 3/4" cem. @ 450' w/350 sx.

Commenced: August 3, 1944
Completed: August 18, 1944

Elevation 1903

Log

Sand	0	-	90
Sand & shells	90	-	165
Shale & red bed	165	-	440
Red bed	440	-	818
Anhydrite	818	-	849
Sand & shale	849	-	1115
Shale & shells	1115	-	1290
Salt & shale	1290	-	1420
Salt, shale & shells	1420	-	1655
Shale & broken lime	1655	-	1820
Lime broken	1820	-	2620
Shale & shells	2620	-	2980
Lime	2980	-	3050
Lime & shale	3050	-	3255
Lime	3255	-	3325
Lime (hard)	3325	-	3385
Lime	3385	-	3430
Shale & shells	3430	-	3564
Lime	3564	-	3630
Lime cherty	3630	-	3663
Lime	3663	-	3815
Lime & shale	3815	-	3850
Shale & lime	3850	-	3890
Shale	3890	-	3904
Lime cherty	3904	-	3917
Cherty conglomerate	3917	-	3936
Cherty lime & shale	3936	-	3950
Shale & lime	3950	-	3975
Lime	3975	-	3990
Shale & sand	3990	-	4026
Shale & sand	4026	-	4032
Dolomite	4032	-	4075

Tops

Anhydrite	819
Lansing Kansas City	3564
Base Kansas City	3775
Conglomerate	3900
Simpson shale	3975
Simpson sand	3996
Arbuckle	4032
Total Depth	4075

3636 - 3640	Soft
3663	Trip
3996 - 4000	Sl. show dead oil
4040 - 4045	Soft, no show

D & A

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

By H. C. Davis
H. C. Davis

Subscribed and sworn to before me this 21st day of August, 1944

Arthur T. Kuhn
Notary Public

My commission expires Oct. 24, 1944

