

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-22,834-0000

LEASE NAME Cornwell

WELL NUMBER #1-30

330 Ft. from N Section Line

1100 Ft. from E Section Line

SEC. 30 TWP. 23 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 4-24-92

Plugging Commenced 4-24-92

Plugging Completed 4-24-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Murfin Drilling Company, Inc.

ADDRESS 250 N. Water, Suite 300 Wichita, KS. 67202

PHONE# (316) 267-3241 OPERATORS LICENSE NO. 30606

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 24, 1992 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filled? by operator If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4015'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	337'	8 5/8"	337'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

50 sx. @ 800', 50 sx. @ 350', 10 sx. @ 40', 15 sx. in Rathole
Total 125 sx. 60/40 Pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson

(Employee of Operator or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well was filed in the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) R.R. 1 Box 183 B

Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1992

Bessie M. DeWerff
 Notary Public
 Bessie M. DeWerff

NOTARY PUBLIC - State of Kansas
 BESSIE M. DEWERFF
 My Appt. Exp. 5-20-93

15-185-22834-0000

DRILLER'S WELL LOG

DATE COMMENCED: 4-15-92
DATE COMPLETED: 4-24-92

MURFIN DRILLING COMPANY, INC.
CORNWELL #1-30
110' W C NW NE NE
SEC. 30-23S-13W
STAFFORD COUNTY, KANSAS

0 - 170 Sand & clay
170 - 337 Sand & Red Beds
337 - 1810 Shale & Lime
1810 - 3520 Lime & Shale
3520 - 3866 Lime
3866 - 3921 Viola Chert
3921 - 4015 Shale & Arb
4015 RTD

ELEVATION: 1897' GR 1902' KB

FORMATION DATA: (log)

Anhydrite 782 (+1115)
B/Anhydrite 803 (+1094)
Tarkio 2798 (-901)
Howard 2947 (-1050)
Topeka 3031 (-1134)
Heebner 3339 (-1442)
Toronto 3359 (-1462)
Douglas 3376 (-1479)
Brown LM 3474 (-1577)
Lansing 3495 (-1598)
BKC 3751 (-1854)
Viola 3869 (-1972)
Simpson Sh 3916 (-2019)
Arbuckle 3966 (-2069)

LTD 4013
RTD 4015

SURFACE CASING:

8 5/8" set @ 337' W/175 sx. 60/40 Poz,
2% gel, 3% CC

A F F I D A V I T

State of Kansas)
County of Barton) ss

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 28th day of April 1992.

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-93

