


Copy All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

15-185-01289-0001



Locate well correctly on above
Section Plat

Stafford County, Sec. 11 Twp. 23 Rge. 13 (E) W (W)
Location as "NE/CNW&SW" or footage from lines ~~SW~~ ~~NE~~ ~~SE~~ ~~SW~~ C SE SW
Lease Owner West Supply Co., Inc.
Lease Name Firebaugh Well No. I-SWD
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8-20-60 _____ 19____
Plugging completed 8-23-60 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4609 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285'	None
				5-1/2"	4065'	2367'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4609' and found it clear.
Ran 550 gal. of sand to 4040' and dumped
5 sacks of cement with dump bailer.
Pulled 5 1/2" casing. Bailed fluid, set 10'
rock bridge from 240" to 230' and ran 30
sacks of cement. Mudded hole to 40', set
10' rock bridge to 30' and ran 10 sacks
of cement to base of cellar.

PLUGGING COMPLETED.

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1960
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of August, 19 60

My commission expires May 20, 1960

Milton J. Volin
Notary Public.

15-185-01289-0001

[Faint, mostly illegible text, possibly a list or index of items.]

[Faint text at the top right, possibly a header or title.]

[Faint text block, possibly a signature or a short paragraph.]

[Handwritten signature]
 [Faint text below signature]

[Faint text block, possibly a date or location.]

[Handwritten signature]
 [Faint text below signature]

[Faint text at the bottom right, possibly a date.]