


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, County. Sec. 11 Twp. 23 Rge. 13W (E) (W) W

Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner Raymond Oil Company, Inc.  
Lease Name FIREBAUGH Well No. 1  
Office Address 410 Fourth National Bank Building  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 2 19 62  
Application for plugging filed January 2 19 62  
Application for plugging approved January 2 19 62  
Plugging commenced January 2 19 62  
Plugging completed January 2 19 62  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot  
Producing formation Depth to top Bottom Total Depth of Well 3880 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	304'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole w/mud to 300', set plug w/1/2 Sx. Hulls,  
25 Sx. cement.  
Fill hole to 40'.  
Set plug 1/2 sx. hulls, 10 Sx. Cement.  
25 Sx. in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 16 1962

CONSERVATION DIVISION  
Wichita, Kansas

2-16-62

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Raymond Oil Company, Inc.  
Address 410 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Pat Raymond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Pat Raymond*  
410 Fourth National Bank Building  
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of February 19 62  
*Bernice Baldt*  
Notary Public.

My commission expires December 10, 1962

Raymond Oil Company, Inc.  
 No. 1 FIREBAUGH  
 SW SW NW 11-23-13W  
 Stafford County, Kansas

ELEVATION:  
 1867 DF  
 1865 GL  
 1870 KB

Contractor: Company Tools - Rig #3  
 Commenced: December 22, 1961  
 Completed: January 2, 1962 (Rotary)

Casing Record  
 8 5/8" @304' w/300 Sx.

15-185-19398-6000

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Sand	125
Red Bed	187
Sand	223
Shale	304
Red Bed and Shale	743
Anhydrite	777
Red Bed and Shale	945
Shale and Shells	1850
Lime and Shale	1915
Sandy Lime with Sand	2030
Lime and Shale	3145
Lime with Sand	3248
Lime and Shale	3410
Lime	3710
Lime and Conglomerate	3760
Lime and Chert	3813
Shale	3824
Shale with Lime	3860
Lime	3880 TD

TOPS

Anhydrite (Drillers)	743
Topeka	3022
Heebner	3276
Brown Lime	3411
Lansing	3427
Conglomerate	3743
Viola	3751
Simpson Shale	3810
Arbuckle	3863
Rotary Total Depth	3880

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 29 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF SEDGWICK )

I hereby certify that the above is true and correct to the best of my knowledge.

Wm M Raymond  
 Wm. M. Raymond, President

Subscribed and sworn to before me this 18th day of January, 1962.

Bernice B. Burt  
 Notary Public



My commission expires  
 December 10, 1962