

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS-67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-185-22,189-0000

LEASE NAME Firebaugh

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to Cons. Div. office within 30 days.

       Ft. from S/N Line of Section (circle one)

       Ft. from E/W Line of Section (circle one)

LEASE OPERATOR Pratt Well Service Inc.

SPOT LOCATION 100'S - NE - SE - NW

ADDRESS P.O. Box 847

SEC. 11 TWP. 23 S. RGE 13 (W)

CITY, STATE, ZIP Pratt, Ks. 67124

COUNTY Stafford

PHONE# (316) 672-2531 OPERATORS LICENSE NO. 5893

Date Well Completed       

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 8-2-96

Date Plugging Completed 8-9-96

The plugging proposal was approved on 8-5-96 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?       

Producing Formation(s)        Depth to Top        Bottom        T.D. 3920

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	304	8 5/8	304	0
		0	3919	5 1/2	3919	1894'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

8-2-96: Dumped 330 gallons of sand + water.  
8-5-96: Top of sand 3565 ft - dumped 5sx. cement.  
8-9-96: Pumped 300# hulls - 10sx. gel - 50sx. cement - 10sx. gel - 100# hulls - 8 5/8 plug - 125sx. cement - 60/40 poz - 6% gel. Max 600# - SIP 100#  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address PO Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pratt Well Service Inc.


STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of operator or contractor) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO Box 847, Inc.



RECEIVED  
 KANSAS CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1996

Dorothy M. Furgason  
 Notary Public

My Commission Expires Feb. 6, 1996

AUG 22 1996

Form CP-4  
 Revised 12-92  
 CONSERVATION DIVISION  
 WICHITA, KS