


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Stafford County, Sec. 11 Twp. 23 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner West Supply Co., Inc.  
Lease Name Firebaugh # Well No. 2(1)  
Office Address Chase, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7-18-60 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 7-27-60 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3866 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	339'	None
				5-1 1/2"	3862'	3035'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3860' and found it clear. Sanded hole to 3845' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing. Bailed hole to 240', set 10' rock bridge to 230' and ran 20 sacks of cement. Mudded hole to 35', set 5' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED.

RECEIVED  
STATE CORPORATION COMMISSION  
8-1-60  
AUG 1 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 60

My commission expires 5-20-64  
Milton J. Volin  
Notary Public.



WELL LOG

Company: NATURAL GAS & OIL CORPORATION

Sec. 11 T. 23S R. 13W  
Stafford County, Kansas  
Location: NW NW SE

Farm: FIREBAUGH #1

Total Depth: RTD 3866  
Commenced: 8/29/55  
Completed: 9/8/55

15-185-13107-0000

Contractor: GREENLAND DRILLING COMPANY

Casing: 8-5/8" 339'  
5-1/2" 3862'

Elevation: 1865 R.B.

Figures Indicate Bottom of Formations

190	Sand w/shale streaks
225	Sand and shale
260	Shale and shells
339	Red Bed w/shells
740	Red Bed and shale
748	Anhydrite
1250	Shale and shells
1400	Shale and shells w/salt
1615	Shale and lime
1675	Lime and shale
1830	Shale and lime w/sandy streaks
2240	Lime and shale
2395	Shale and lime
2565	Lime and shale
2755	Shale and lime
2880	Shale and lime w/sandy streaks
3238	Lime and shale
3325	Shale and lime
3403	Shale and sandy lime
3406	Brown lime
3414	Shale
3652	Lime
3739	Shale and lime
3779	Shale and chert
3800	Lime, shale and chert
3809	Shale and sand
3812	Sand and shale
3861	Shale and sand
3866	Arbuckle
3866	T.D.

TOPS:

Heebner	3265
Brown Lime	3403
Lansing	3417
Conglomerate	3738
Viola	3755
Simpson	3797
Arbuckle	3861
T.D.	3866

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 6 1960

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Richard S. Davis, of the Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Firebaugh well.

Richard S. Davis

Subscribed and sworn to before me this 13th day of September, 1955.

Verdina B. Rutledge, Notary Public

My commission expires March 15, 1956