


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-185-13106-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 11 Twp. 23S Rge. (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Graham-Michaelis Drilling Company
Lease Name Firebaugh Well No. 1
Office Address 211 North Broadway, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 9-28-55 19
Application for plugging filed August 10, 1960 19
Application for plugging approved August 11, 1960 19
Plugging commenced August 13, 1960 19
Plugging completed August 17, 1960 19
Reason for abandonment of well or producing formation decline of production

If a producing well is abandoned, date of last production July 29, 1960
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas
Producing formation Arbuckle Depth to top 3859' Bottom 3860' Total Depth of Well 3864 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	oil	3859'	3860'	5 1/2"	3860'	3216.09'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand to 3850' and dumped 5 sx cement. Pumped 38 bbls of jell mud, set plug and 75 sx cement. Filled surface pipe from 225' to base of cellar with cement.

STATE CORPORATION COMMISSION
SEP 12 1960
CONSERVATION DIVISION
Wichita, Kansas
9-12-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Company, Inc.
Address P. O. Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John L. James (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John L. James
211 North Broadway, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1960

My commission expires May 24, 1961
Mildred A. Fisher Notary Public



WELL LOG

15-185-13106-0000

COMPANY MICHAELIS DRILLING COMPANY

SEC. 11 T. 21S R. 10E

FARM Firebaugh

NO. 1


LOC. SE SE NW

TOTAL DEPTH 366'

COUNTY Stafford

COMM. September 9, 1955 COMP. September 12, 1955

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 310'
5-1/2" @ 366'

ELEVATION - -

PRODUCTION - -

FIGURES INDICATE BOTTOM OF FORMATIONS

25	Sand
250	Gray Shale
310	Red Bed
515	Red Bed & Sand
710	Red bed & shale
750	Anhydrite
1000	Shale-chert
1045	Lime & Shale
1075	Lime
2000	Lime & shale
2300	Shale
2540	Lime & Shale
3410	Shale
2735	Lime
2745	Chert
2800	Violet Chert & Lime
3035	Shale & Lime
3359	Shale
3854	Arbuckle
3864	T.O.

RE: STATE CORP. ED COMMISSION

AUG 11 1960

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of SEDFIELD } SS:

I, Robert F. White of Garvey Drilling Company

do hereby state that the above and foregoing is a true and correct copy of the log of the 11 Firebaugh well

Robert F. White
Attorney In Fact

Subscribed and sworn to before me this 3rd day of October, 1955

My Commission Expires: August 8, 1957

Allen M. ...
NOTARY PUBLIC