


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County. Sec. 11 Twp. 23S Rge. 13W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines SN/SN/NE
Lease Owner Columbia Supply Co.
Lease Name Ward Well No. #1
Office Address East 10th, Great Bend Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 7-16 1959
Plugging completed _____ 7-25 1959
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3867' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	surface	
				5 1/2"	casing	3,126'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3867'.
Plugging started 7-16-59. Finished 7-25-59.
Plugged off bottom and sanded back to 3840'. Dumped 5 sacks of cement.
Worked and shot pipe. Shot 5 1/2" casing at 3,126'. Layed down pipe
and squeezed well as follows: Squeezed well with 25 sacks of mud and 75
sacks of cement. Well completed.

RECORDED
STATE CORPORATION
8-359

AUG 3 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1959

Betty S. Edman
Notary Public.

My commission expires September 8, 1960

PLUGGING
FILE SEC. 11 T. 23 R. 13W
BOOK PAGE 57 LINE 33

DRILLING RECORD

15-185-00820-0000

Ralph L. Ward Well No. 1
SW SW NE Sec 11023S-13W
Stafford County, Kansas

Casing Record

270' of 8-5/8" OD Casing
cemented with 225 sacks.
3857' of 5 1/2" OD Casing
cemented with 75 sacks.

Work commenced 6/22/55
Drilling Commenced 6/22/55
Drilling Completed 7/4/55
Work Completed 7/5/55

WELL LOG

Sand	0 to 170
Sand & Clay	170 to 235
Clay & Shale	235 to 250
Red Bed	250 to 735
Anhydrite	735 to 765
Shale	765 to 900
Shale & Shells	900 to 1085
Salt & Shale	1085 to 1250
Shale & Shells	1250 to 1425
Shale	1425 to 1510
Shale & Lime Streaks	1510 to 1665
Lime & Shale	1665 to 3309
Lime & Shale, Hunks Chert	3309 to 3400
Lime & Shale	3400 to 3483
Lime	3483 to 3505
K.C. Lime	3505 to 3540
Lime	3540 to 3650
Lime & Shale	3650 to 3654
Lime	3654 to 3729
Viola Chert	3729 to 3763
Lime Cherty	3763 to 3796
Simpson	3796 to 3833
Shale	3833 to 3856
Arbuckle	3856 to 3867 TD

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1959
CONSERVATION DIVISION
Wichita, Kansas

C E R T I F I C A T I O N

State of Oklahoma, County of Tulsa, SS

I, J. L. Stackpole of the Iron Drilling Company, Certify that the accompanying is a true and correct log of the above described well.

Signed

J. L. Stackpole

Subscribed to and Sworn before me this 26th day of August, 1955.

B. Michel

Notary Public

My commission expires Feb. 28, 1956

PLUGGING
FILE SEC. 11 T. 23 R. 13W
BOOK PAGE 51 LINE 27