

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5153 EXPIRATION DATE June 30, 1983

OPERATOR Texaco Inc. API NO. None

ADDRESS P. O. Box 2420 COUNTY Finney

Tulsa, OK 74102 FIELD Damme

** CONTACT PERSON B. A. Batson PROD. FORMATION Herrington-

PHONE 918-743-5311 Krider

PURCHASER None LEASE Garden City Co., "B"

ADDRESS WELL NO. 4

DRILLING Garvey Drilling Co. 660 Ft. from North Line and

CONTRACTOR CONTRACTOR ADDRESS 660 Ft. from West Line of

Wichita, KS the NW (Qtr.) SEC 5 TWP 22 S RGE 33 W

PLUGGING None WELL PLAT (Office Use Only)

CONTRACTOR CONTRACTOR ADDRESS

TOTAL DEPTH 4809 PBD 2793

SPUD DATE 1-27-72 DATE COMPLETED 3-1-72

ELEV: GR 2891 DF 2896 KB 2898

DRILLED WITH ROTARY TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 418' DV Tool Used? no

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T


B. A. Batson, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

B. A. BATSON ASST DIST MGR

B. A. Batson (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 10th day of January, 1983



MY COMMISSION EXPIRES: January 25, 1987

Signature of Eloise Brandon, Notary Public, Commission Expires JAN 25 1987

** The person who can be reached by phone regarding any questions concerning this information.

1-13-83

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Texaco Inc.

LEASE Garden City Co SEC. 5 TWP. 22S RGE. 33W

FILL IN WELL LOG AS REQUIRED: "B" #4

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	DEPTH
Sand & Clay	0	419	
Shale	419	1115	
Shale & Anhydrite	1115	2025	
Shale & Lime	2025	2345	
Shale & Red Bed	2345	2845	
Shale & Lime	2845	2930	
Shale, Lime & Sand	2930	3820	
Shale & Lime	3820	4040	
Lime	4040	4809	

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	13-3/4"	9-5/8	32#	423	50/50 Poz	450	3% CaCl
Production	8-3/4"	5-1/2		4808	50/50 Poz	225	10% Salt

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
					4701-4710
TUBING RECORD			2	1/2"	2531-39'
Size	Setting depth	Packer set at	2	1/2"	2543-53'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2000 gal 15% HCL & 18.75 X 18.75 Sd-Foam Acid Frac	2543-53' & 2531-39'

Date of first production 11-25-82	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls. Gas 135 MCF Water % 6 bbls. Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold) Sold		Perforations 2543-53' & 2531-39'