

1080137

15-185-19417-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE NW SE 15, Sec. 15, T 23 S, R 14 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202 2310 feet from W/S section line
TECHNICIAN'S PLUGGING REPORT 1650 feet from W/E section line
Operator License # 5238 Lease Name Ward 'B' Well # 1 SWD
Operator: Petroleum, Inc. County Stafford
Name & P. O. Box 1447 Well Total Depth 3818 feet 124.09
Address Great Bend, KS 67530 Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:05 pm Day: 4 Month: May Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2 set at 3816' Open Hole

1st plug sand back to 3760' and dump 10 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

and release 8 5/8" rubber plug and pump an additional 100 sx cement

Maximum pressure 900# and shut-in pressure 350#

Signed J. A. Meff
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:00 pm Day: 4 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 3816' Open Hole

1st plug sanded back to 3760' and dumped 10 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack

hulls and released 8 5/8" rubber plug and pumped an additional 100 sx cement.

Maximum pressure 900# and shut-in pressure 350#.

Remarks: They recovered 2500' of 5 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Allied.

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

INVOICED

DATE 5-14-84

INV. NO. 1506

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1984

CONSERVATION DIVISION
Wichita, Kansas

Signed J. A. Meff
(TECHNICIAN)

5-11-84

FORM CP-2/3
Rev. 9-82