

S-27

To: 1 040283  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,590 0000  
SW SE NE, SEC. 16, T 23 S, R 13 WAE  
2970 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5097  
Operator: Martin Oil Producers, Inc.  
Name & Address: 1010 Union Center  
Wichita, KS 67202

Lease Name Meryle Heyen Well # 1  
County Stafford 126.91  
Well Total Depth 3905 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company License Number 5418  
Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 4 a.m. Day: 27 Month: 5 Year: 19 89

Plugging proposal received from Ed Shrapel  
(company name) Allen Drilling Company (phone) 316-793-3582

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 755-778'  
1st plug at Arbuckle if into it 50' or good drilling brake with 40 sx cement,  
2nd plug at 780' with 50 sx cement,  
3rd plug at 300' with 40 sx cement,  
4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8 a.m. Day: 27 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3865' with 40 sx cement,  
2nd plug at 780' with 50 sx cement,  
3rd plug at 300' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED 6-16-89  
STATE CORPORATION COMMISSION  
JUN 16 1989

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 6-21-89  
INV. NO. 25700

Signed Stephen J. Pfeifer (TECHNICIAN)

FORM MUST BE TYPED  
FORM C-1 12/88

State of Kansas  
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 5 15 89  
month day year

SW SE NE Sec 16 Twp 23 S, Rg 13 East West

OPERATOR: License # 5097  
Name: Martin Oil Producers, Inc.  
Address: 1010 Union Center  
City/State/Zip: Wichita, KS 67202  
Contact Person: Joseph E. Moreland, Jr.  
Phone: 264-0352

2970 feet from South line of Section  
990 feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5418  
Name: Allen Drilling Co.  
Well Drilled For: Well Class: Type Equipment:

County: Stafford  
Lease Name: Meryle Heyen Well #: 1  
Field Name:  
Is this a Prorated Field? yes X no  
Target Formation(s): K.C. - Arbuckle  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 1871 feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 100/120  
Depth to bottom of usable water: 230  
Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 275  
Length of Conductor pipe required: No  
Projected Total Depth: 390.0  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  
X well farm pond X other

X Oil Inj Infield X Mud Rotary  
Gas Storage X Pool Ext. Air Rotary  
OAWD Disposal Wildcat  
Seismic; # of Holes

If OAWD: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, total depth location:

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Set 275' 0" of 8 3/8" SX  
PUSHER Ed Shrapel  
TD 390.5 FORMATION  
SURFACE PIPE 8 3/8" @ 275'  
ANHYDRITE 778 ELEVATION  
STARTING TIME & DATE 4 Apr 5-89  
COMPLETION TIME & DATE  
1st PLUG @ 780 FT. WI 50 SX  
2nd PLUG @ 300 FT. WI 40 SX  
3rd PLUG @ 40 FT. WI 10 SX  
4th PLUG @ FT. WI SX  
RAT HOLE CIRCULATED WI 15 SX  
MOUSE HOLE CIRCULATED WI SX  
WATER WELL PLUGGED WI NON V SX  
CEMENT COMPANY Hall  
TECHNICIAN S.P.  
60/40/6"

DWR Permit #:  
Will Cores Be Taken? yes X no  
If yes, proposed zone:  
250' Alt. I Req.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 16 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Vertical scale table with depth markings from 2310 to 330.

6 months of effective date.)  
Spud date: Agent:

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field prorations orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.