

1 120868

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,456 -0000
C S/2 NW, SEC. 16, T 23 S, R 13

TECHNICIAN'S PLUGGING REPORT

Operator License # 5670

Operator: Basye Well Servicing Company
Name & Address: P.O. Box 149
Stafford, KS 67578

3300 feet from S section line
3960 feet from E section line

Lease Name Aitken Well # 1

County Stafford

Well Total Depth 3728 121.16 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well _____ Gas Well Input Well _____ SWO Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Basye Well Servicing Company License Number 5670

Address P.O. Box 149; Stafford, KS 67578

Company to plug at: Hour: 9 a.m. Day: 17 Month: 12 Year: 19 93

Plugging proposal received from Marvin Basye

(company name) Basye Well Servicing Co. (phone) 316-234-5235

Perfs: 4 1/2" at 3727' w/75 sx cement, Perfs at 3646-52, 3656-60', 3530-40'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 17 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3200' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-350 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1488' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE DEC 29 1993

INV. NO. 39573 12-17

Signed *Duane Rankin* (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1993
12-21-93
CONSERVATION DIVISION
Wichita, Kansas