

To: 1 031397
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

*Rec'd
6-1-96*

Operator License # _____

Operator: Kansas Corporation Commission
Name: _____
Address: _____

API NUMBER 15- Drilled 9/55 15-185.00821/4600
NE NW NW, SEC. 20, T 23 S, R 13 W & R

_____ 4950 feet from S section line

_____ 4290 feet from E section line

Lease Name Schulz Well # 2

County Stafford

Well Total Depth 3962 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 168

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: _____ Day: 6 Month: 4 Year: 19 96

Plugging proposal received from Steve Durrant

(company name) KCC (phone) 316-225-6760

logs: 5 1/2" at 3956', Perfs at approx. 3633-47', Anhydrite at 840', PBSD 3500'

Run tubing to 3500', spot 50 sx cement, run tubing to 1500' and spot 50 sx cement,
pull tubing to 830' and spot 50 sx cement, pull tubing to 300' and fill hole with 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a. Day: 10 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 4/6/96 Ran 2 3/8" tubing to 3302' and spotted 50 sx Class H w/2% gel 3% cc cement. Ran tubing to 868' and pumped 50 sx cement. Pulled tubing to 430' and pumped 50 sx cement. Pulled tubing to 210' and attempted to circulate cement. No circulation throughout staging. 4/8/96 Ran wireline and found TD at 233'?. Ran tubing to 788' and pumped 300 lbs. hulls mixed in 20 sx gel followed by 50 sx 60/40 Pozmix 2% gel 3% cc at 788'. No circulation. Ran tubing to 788'. No fill. Pumped 300 lbs. hulls mixed in 20 sx gel followed (over)

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 1264' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

PLUGGING REPORT CONTINUED:

by 150 sx 60/40 Pozmix 2% gel 3% cc. No circulation.

4/9/96 Ran tubing and found TD at 679'. Pumped 300 lbs. hulls mixed in 20 sx gel followed by 50 sx 60/40 Pozmix 2% gel 3% cc. No circulation.

Waited 3 hours and ran tubing. Found TD at 566. Pumped 300 lbs. hulls mixed in 20 sx gel and 200 sx 60/40 Pozmix 2% gel 3% cc. Good circulation last part of job. No gel or cement to surface. Waited 3 hours and tagged cement at 340'.

Pumped 8 sx gel with hulls and started circulating gel to surface. Good returns.

Pumped 200 sx 60/40 Pozmix 2% gel 3% cc. Good circulation. No cement to surface.

4/10/96 Ran tubing and found cement top at 233'. Pumped 175 sx 60/40 Pozmix 2% gel 3% cc cement to surface. Plug job completed at 10:45 a.m. on 4/10/96.

4/11/96 Cement to surface.

Also witnessed by Richard Lacey.