

TO: -  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-00030-00-00<sup>01</sup>  
Spot: CSENE SW Sec/Twnshp/Rge: 26-22S-12W  
990 feet from N Section Line, 330 feet from E Section Line  
Lease/Unit Name: SPANGENBERG Well Number: 1  
County: STAFFORD Total Vertical Depth: 3644 feet  
Conductor Pipe: Size \_\_\_\_\_ feet: 76/18.43  
Surface Casing: Size 8.625 feet: 235 WITH 200 SX CMT  
Production: Size 5.5 feet: 3640 WITH 150 SX CMT  
Liner: Size 4 feet: 3644

Operator License No.: 4365  
Op Name: ANSTINE-MUSGROVE  
Address: PO BOX 2444  
PONCA CITY, OK 74602

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/20/2002 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3400' & 4 SX CMT. PERFORATE AT 650'. PUMP 300 SX CMT DOWN 4 1/2". CIRCULATE CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 12/20/2002 11:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:  
PBTD 3540'. PERFS AT 3465-75'. SANDED TO 3400' & 4 SX CMT. PERFORATED 5 1/2" & 4 1/2" AT 650'. PUMPED 300 SX CMT DOWN 4 1/2" CIRCULATED CMT UP 5 1/2" X 4 1/2" ANNULUS & 8 5/8" X 5 1/2" ANNULUS.

RECEIVED  
DEC 30 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED  
Plugged through: CSG  
12-23-02

District: 01 Signed Richard W. Lacey (TECHNICIAN)  
**RECEIVED**  
DEC 23 2002  
KCC Dodge City  
**INVOICED**  
DATE 12-31-02  
INV. NO. 2003061003