

1 120908

3-29

API NUMBER 15-185-21,938-0600

195 ✓

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SW, SEC. 15, T. 22 S, R. 13 W/K
990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Lease Name Ochel Well # 1

Operator: RAMA Operating Co., Inc.

County Stafford

Name & Address P.O. Box 159

Well Total Depth 3870 125.77 feet

Stafford, KS 67578

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 5:15 p.m. Day: 29 Month: 3 Year: 19 94

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

logs: 5 1/2" at 3869' w/150 sx cement, Perfs at 3830-32'

1st plug sand back to 3780' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 29 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3770' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-500 psi and shut in 200 psi.

Plate and 5 1/2" collar welded in 8 5/8" surface casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION
APR 01 1994 4-1-94
CONSERVATION DIVISION
Wichita, Kansas

INVOICED (if additional description is necessary, use BACK of this form.)
observe this plugging.

DATE APR 8 1994

Signed [Signature] (TECHNICIAN)

INV. NO. 40298