

12-29

To: 1 120200

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

NW NW SE, SEC. 15, T 22 S, R 13 W/E

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

RECEIVED
STATE CORPORATION COMMISSION
JAN - 4 1989

Lease Name Howard "A" Well # 1

Operator: Graham-Michaelis Corporation
Name & Address

County Stafford 123.76

P.O. Box 247

Well Total Depth 3808 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Graham-Michaelis Corporation License Number 5134

Address P.O. Box 247, Wichita, KS 67201

Company to plug at: Hour: 10 a.m. Day: 29 Month: 12 Year: 19 88

Plugging proposal received from Norman Rodie

(company name) Graham-Michaelis Corporation (phone) 316-264-8394

were: 5 1/2" at 3798', 5 1/2" casing squeezed from 570' to 261' to surface, observed cement from hole cut by welder, Perfs at 3506-52'

1st plug pump 2 sx hulls, 25 sx cement, gel, 50 sx cement, gel and 125 sx cement,

2nd plug pump 100 sx cement down backside.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped into 5 1/2" casing with 150 lbs. hulls, 25 sx cement, 25 sx gel, 100 lbs. hulls, and 125 sx cement.

8 5/8" X 5 1/2" annulus full of cement.

Pumping pressure 0-1000 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 1-9-89

Signed *Paul Luthi* (TECHNICIAN)

INV. NO. 23553

12-29