

1060157

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW NW SW, SEC. 15, T 22 S, R 13 W/EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,943-0000

1650 feet from XWS section line

330 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6385

Lease Name Ochel Well # 2

Operator: Ruthven, Inc.

County Stafford

Name & Address Box 272

Well Total Depth 3880 126.10 feet

Russell, KS 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Revlin Drilling, Inc. License Number 5671

Address Box 293, Russell, KS 67665

Company to plug at: Hour: 1:00 am Day: 11 Month: February Year: 19 84

Plugging proposal received from Stanley C. Lingreen

(company name) Revlin (phone) 913-346-5618

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 760' with 50 sx cement

2nd plug at 340' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Paul A. Luthie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:00 am Day: 11 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 760' with 50 sx cement, 2nd plug at 340' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement. 5th plug to circulate rathole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
2-15-84  
FEB 15 1984  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Use 60/40 Pozmix with 2% gel, 3% cc. by Halliburton  
(if additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed Paul A. Luthie  
(TECHNICIAN)

DATE 2-23-84

INV. NO. 0355