

12-29 15-185-11210-0000

To: 1 120199

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- N/A

TECHNICIAN'S PLUGGING REPORT

S/2 NW SE, SEC. 15, T 22 S, R 13 W/E

1650 feet from S section line

1980 feet from E section line

Operator License # 5134

Lease Name Howard "A" Well # 2

Operator: Graham-Michaelis Corporation  
Name & Address P.O. Box 247  
Wichita, KS 67201

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
1-4-89  
IAM - 4 1989

County Stafford 123.76

Well Total Depth 3808 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Graham-Michaelis Corporation License Number 5134

Address P.O. Box 247, Wichita, KS 67201

Company to plug at: Hour: 11:30 a.m. Day: 29 Month: 12 Year: 19 88

Plugging proposal received from Norman Rodie

(company name) Graham-Michaelis Corporation (phone) 316-264-8394

were: 5 1/2" at 3792' Perfs at 3510-3576' PBTD 3505' 4 1/2" liner set at 2993' cement circ.  
1st plug pump 2 sx hulls, 25 sx cement, 22 sx gel, 125 sx cement,

2nd plug pump 100 sx cement on backside.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1 p.m. Day: 29 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 250 lbs. hulls, 25 sx cement, 15 sx gel, 50 lbs. hulls and 100 sx cement.

Pressured to 550 psi on 8 5/8" X 5 1/2" annulus with 1/2 barrel.

Pumping pressure 0-1000 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-9-89

INV. NO. 23554

12-29

Signed *Paul Luthi* (TECHNICIAN)