

4-041732

11-8 15-009-19301-0000  
API Number: 15- - 1-28-65

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NW SW NE /4 SEC. 33, 16 S, 11 W  
3330 feet from S section line  
2310 feet from E section line

Operator license# 4707

Lease: Bernstorff-Janke Well # 5

Operator: Carl Boxberger Oil, Inc.

County: Barton

Address: P.O. Box 1604  
Great Bend, Kansas 67530

Well total depth 3346 108.75 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 7 Inch @ 406 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing - Mike's Testing License# -

Address: Great Bend, Kansas 67530 - Chase, Kansas 67525

Company to plug at: Hour: 1:00 P.M. Day: 8 Month: November Year 1995

Plugging proposal received from: Mike Kelso

Company: Mike's Testing and Salvage Phone:

Were: 4 1/2" casing set at 3341' w/N/A sxs cement. Perf. at Topeka and Kansas City open.  
Perforated salt at 1450' - Anhy. at 760' - Dakota at 375' - W.L.M. at 1900' - T.O.F. at 1300'.  
2 7/8" liner at 3193' with T.O.C. at 1935'.  
Ordered 250 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel - Herb Deines

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 3:30 P.M., Day: 8, Month: November, Year: 1995

Actual plugging report: R.U. perforators to shot casing at 1450' - 760' - 375'. R.U. cementers to 2 7/8" tubing. Squeezed 165 sxs cement with 400# hulls. Max. P.S.I. 700#. Hooked-up to 4 1/2" annulus and squeezed 35 sxs cement to 500#. Shut in same.

NOV 29 1995  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
11-29-95

Remarks: Cement circulated 2 7/8" x 4 1/2" casing annulus.  
Condition of casing(in hole): GOOD X BAD  
Anhy.plug: YES X NO  
Bottom plug(in place): YES X, CALC X, NO  
Dakota plug: YES X, NO  
Plugged through TUBING X, CASING X. Elevation: GL

I did[ X ] / did not[ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

TD.

INVOICED  
NOV 30 1995  
DATE  
INV. NO. 44155