

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19260-00-00
Spot: NENWNE Sec/Twnshp/Rge: 33-33S-11E
4633 feet from S Section Line, 1434 feet from E Section Line
Lease Name: GRIFFITH Well #: 17
County: CHAUTAUQUA Total Vertical Depth: 1200 feet

Operator License No.: 33157
Op Name: R. D. ENERGY, INC.
Address: 905 N MONTGOMERY
SEDAN, KS 67361

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 06/25/2007 10:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' plug at TD, 50' plug at 600' and 350' to surface. Perforate at 350'.

Plugging Proposal Received By: LARRY MARCHANT WitnessType: NONE
Date/Time Plugging Completed: 06/25/2007 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Well was plugged prior to my employment with the KCC. Information came from plugging contractor invoice #6995. I found well with metal detector, gps'd and changed footages accordingly. Ran 1" to 1000' gelled hole and spotted 15 sack plug. Pulled up to 600' and spot 15 sack plug. Pulled 1" and perforate casing at 350'. Ran back into 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 152 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

4-24-17
KCC WICHITA
APR 24 2017
RECEIVED

RECEIVED
KCC DIST # 3
APR 19 2017
CHANUTE, KS

DS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)