

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01303-00-00
Spot: NWNENENW Sec/Twnshp/Rge: 14-24S-12E
5100 feet from S Section Line, 3000 feet from E Section Line
Lease Name: SULLIVAN Well #: 29
County: GREENWOOD Total Vertical Depth: 1796 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1738		100 SX
SURF	8.625	135		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2017 10:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Revd. from: DWAIN STOUT Company: _____ Phone: (316) 640-9072

Proposed Pump gel from TD into casing. Set 50 ft. cement plug at bottom of casing. Shoot off casing at 800 ft. Set a 50 ft. cement
Plugging plug at 800 ft. Pull tubing to 150 ft. and cement to surface.
Method:

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1700', pumped 20 sxs cement, pull tubing to 800', pumped 20 sxs cement, pulled tubing to 150', pumped 60 sxs cement to surface, gel spacers between cement plugs, casing shot @ 800' & 150'.

Perfs:

INVOICED
APR 28 2017

RECEIVED
KCC DIST # 3
FEB 27 2017
CHANUTE, KS

MH
4-27-17
KCC WICHITA
APR 27 2017
RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed Mick Deffen
(TECHNICIAN)