

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22390-00-00
Spot: SWNESESE Sec/Twnshp/Rge: 10-18S-30W
697 feet from S Section Line, 411 feet from E Section Line
Lease Name: SHIRLEY Well #: 2-10
County: LANE Total Vertical Depth: 4640 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>3842</u>	<u>PC</u>	<u>5.5</u>	<u>2148</u>		<u>WITH 175 SX CMT</u>
Op Name: <u>LARSON ENGINEERING, INC. DBA LAR</u>	<u>PROD</u>	<u>5.5</u>	<u>4636</u>	<u>0</u>	<u>WITH 125 SX CMT</u>
Address: <u>562 W STATE RD 4</u> <u>OLMITZ, KS 67564</u>	<u>SURF</u>	<u>8.625</u>	<u>262</u>		<u>WITH 175 SX CMT</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2017 1:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT WITH HULLS. RTIH TO 2250' & CIRCULATE CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 04/11/2017 4:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

RAN TBG TO 4226'. SQUEEZED PERFS WITH 25 SX CMT & 200# HULLS. PULLED TBG TO 2246' & CIRCULATED CMT TO SURFACE WITH 225 SX CMT. PULLED TBG & TOPPED OFF WITH 35 SX CMT. PUMPED 10 SX CMT DOWN BACKSIDE. PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
4367	4369		
4355	4357		
4354	4369		
4273	4275		

INVOICED
APR 28 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL.

Plugged through: TBG

District: 01

4-13-17
RECEIVED
APR 13 2017
KCC DODGE CITY

Signed Larry Harris ECRS
(TECHNICIAN)