

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22577-00-00
Spot: E2NWNENE Sec/Twnshp/Rgc: 9-19S-27W
5008 feet from S Section Line, 785 feet from E Section Line
Lease Name: RIEBEL Well #: 1-9
County: LANE Total Vertical Depth: 4750 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	2089		WITH 150 SX CMT
PROD	5.5	4748	0	WITH 300 SX CMT
SURF	8.625	306		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2017 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING Phone: (620) 793-3051

Proposed Plugging Method: PUMP BOTTOM WITH 50 SX CMT & 200# HULLS. PLUG AT 2100' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2017 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

RAN TBG. PUMPED BOTTOM WITH 50 SX CMT & 100# HULLS. PULLED TO 2100' & CIRCULATED TO SURFACE WITH 220 SX CMT. PULLED TBG & TOPPED OFF WITH 30 SX CMT. PUMPED 20 SX CMT DOWN BACKSIDE. PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
4638	4642		
4630	4634		

INVOICED
APR 28 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Larry Harris ECRS
(TECHNICIAN)
SR

INVOICED Form CP-2/3
APR 28 2017