

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00324-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 20-22S-34W
1982 feet from S Section Line, 3273 feet from E Section Line
Lease Name: BARRETT UNIT Well #: 1
County: FINNEY Total Vertical Depth: 2634 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1050		
PROD 7		2462	0	WITH 100 SX CMT
SURF	10.75	274		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/14/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2017 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

4/14/17: PUMP 120 SX CMT WITH 200# HULLS THROUGH TBG AT 2430'. CIRCULATED WATER TO SURFACE. AFTER 2 HOURS TAG TOC IN 7" CASING AT 1990'. SET CIBP @ 1050' SDFD. 4/17/17: RUN PACKER ON TBG TO 700'. ATTEMPT TO PUMP INTO CASING LEAKS @ 948-962'. 1/4 BPM @ 500#. INSUFFICIENT RATE TO SQUEEZE CMT. TOOH. PERFORATE 4 HOLES AT 1025'. RUN TBG & PACKER TO 700'. INJECTION RATE 1 1/2 BPM AT 500#. PUMP 80 SX CMT WITH 40# HULLS IN LAST 40 SX CMT. DISPLACE TO 800' LEAVING 40 SX CMT INSIDE THE 7" AND 40 SX CMT OUT THE 7". PERFORATE 4 HOLES AT 307'. SDFD. 4/18/17: CIRCULATE CMT FROM 307' TO 0' USING 225 SX CMT LEAVING THE 7" & 7" X 10 3/4" ANNULUS FULL OF CMT. TOP OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2488	2625		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

4-19-17

Signed

Ken Jehlik
SA

(TECHNICIAN)
INVOICED

RECEIVED
APR 19 2017

KCC DODGE CITY

APR 28 2017

Form CP-2/3