

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21308-00-00
Spot: E2W2E2W2 Sec/Twnshp/Rge: 25-24S-34W
2685 feet from S Section Line, 3471 feet from E Section Line
Lease Name: LAYMAN Well #: 3-2-25
County: FINNEY Total Vertical Depth: 3175 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3164	0	WITH 490 SX CMT
SURF	8.625	555		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/13/2017 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2017 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 100 SX CMT FROM 2899' TO 1800' DOWN 5 1/2" CASING. PUMP 15 BBL SPACER FROM 1800' TO 1200'. PUMP 125 SX CMT FROM 1200' TO 0'. PRESSURED TO 400#. HOLDING. PUMP 15 SX CMT DOWN THE 5 1/2" X 8 5/8" ANNULUS. PRESSURE TO 300#. HOLDING. TOP OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2883	2899		


Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

4-19-17

Signed



(TECHNICIAN)

RECEIVED
APR 19 2017
KCC DODGE CITY



SA

INVOICED
APR 23 2017

Form CP-2/3