

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-21129-00-00  
Spot: SENESWNW Sec/Twnshp/Rge: 17-16S-7W  
3545 feet from S Section Line, 4246 feet from E Section Line  
Lease Name: HOFFMAN Well #: 1-17  
County: ELLSWORTH Total Vertical Depth: 2200 feet

Operator License No.: 5399

Op Name: TREK AEC, LLC

Address: 200 W DOUGLAS, SUITE 101  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2192		175 SX
SURF	8.625	270		175 SX
T1	2.375	1768		

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 04/14/2017 1:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: TANNER NELSON

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 755-2571

Proposed  
Plugging  
Method:

As per Kansas Corporation Commission's Rules and Regulations, as per their recommendations.

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/14/2017 3:15 PM

KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

**Perfs:**

MIRU, pull rods and tubing. Run tubing to 1715' and pump 25 sx's common cement with 100 #s cotton hulls. Cut casing off at 830' and pump 35 sx's common with 3% CC. Pull casing up to 500'. Wait awhile and tag cement at 520'. Circulated cement from 500' on up to surface. Pulled casing out and topped off.

Top	Bot	Thru	Comments
1778	1782		
1768	1782		

Remarks: QUALITY OIL-WELL CEMENT TICKET #6652. TA N.O.V.

Plugged through: CSG

District: 02

Signed

Judd Klock DISTRICT SUPERVISOR  
(TECHNICIAN)

INVOICED

APR 23 2017

INVOICED

APR 28 2017

Form CP-2/3