

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-21124-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 27-16S-7W
3176 feet from S Section Line, 4608 feet from E Section Line
Lease Name: REED Well #: 1-27
County: ELLSWORTH Total Vertical Depth: 1910 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5399</u>	<u>PROD</u>	<u>4.5</u>	<u>1908</u>		<u>175 SX</u>
Op Name: <u>TREK AEC, LLC</u>	<u>SURF</u>	<u>8.625</u>	<u>239</u>		<u>165 SX</u>
Address: <u>200 W DOUGLAS, SUITE 101</u> <u>WICHITA, KS 67202</u>	<u>T1</u>	<u>2.375</u>	<u>1833</u>		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/19/2017 11:45 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TANNER NELSON Company: QUALITY WELL SERVICE, INC. Phone: (620) 755-2571

Proposed Plugging Method: As per Kansas Corporation Commission's Rules and Regulations, as per their recommendations.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 04/19/2017 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, pull rods and tubing. Run tubing to 1750' and pump 25 sx's common cement with 100#'s cotton hulls. Cut casing at 850' and pull up 1 jt and pump 35 sx's common cement with 3% CC. Pull casing to 500' and wait awhile. Tag cement at 625'. Pump and circulate cement from 500' to surface. Pull casing out and top off.

Perfs:

Top	Bot	Thru	Comments
1816	1820	CSG	

Remarks: QUALITY OIL - WELL CEMENT TICKET #6653.

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

APR 28 2017

Form CP-2/3