

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-22286-00-00
Spot: SESWNENE Sec/Twnshp/Rge: 1-29S-14E
1100 feet from N Section Line, 965 feet from E Section Line
Lease Name: DOCIA BATES Well #: 5
County: WILSON Total Vertical Depth: 1088 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1080		96 SX
SURF	5	45		11 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/12/2016 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run 1" to TD of well and pump 15ppg portland cement to surface. Trip pipe out and top well off at surface.

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL
Date/Time Plugging Completed: 05/12/2016 12:00 PM KCC Agent: ALAN DUNNING

4-20-17

Actual Plugging Report:

A one inch cement string was lowered to 1065 ft and 30 sacks of cement pumped. Did not get cement to surface so will trip out of hole and allow cement to set. Tag cement the next day, 5-13-16, at 780 ft. Cement was then pumped to surface. The one inch cement string was pulled to 350 ft and cement pumped. The cement string was then removed and the well topped off. A total of 62 sacks of portland cement were used to plug well.

Perfs: **KCC WICHITA**
APR 20 2017
RECEIVED

RECEIVED
KCC DIST #3
APR 14 2017
CHANUTE, KS


AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)



INVOICED

APR 28 2017