

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-22748-00-01
Spot: NWNWSENE Sec/Twnshp/Rge: 1-29S-14E
1325 feet from N Section Line, 1225 feet from E Section Line
Lease Name: DOCIA BATES Well #: 10
County: WILSON Total Vertical Depth: 1092 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1090		111 SX
SURF	5	50		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2016 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run 1" pipe to bottom and pump cement to surface. Trip out out of hole and top well off using 15ppg portland cement.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 05/18/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:
The 2.875 inch longstring was hooked onto directly. 4 bbls of water was pumped to establish circulation. The well was then pumped full of cement that contained cottonseed hulls. The well was then shut in with 900 psi which held. A total of 42 sacks of portland cement were used to plug well.

Perfs: 4-20-17

Top	Bot	Thru	Comments
799	804		
786	792		KCC WICHITA
			APR 20 2017
			RECEIVED
			RECEIVED
			KCC DIST #3
			APR 14 2017
			CHANUTE, KS
			AD

Remarks:
Plugged through: CSG

District: 03 Signed Alan Dunning
(TECHNICIAN)

INVOICED
APR 28 2017