

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
DEC 8 1964
12-8-64
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Drillers Production Company, Inc.Complete Address: 1020 Union National Bldg., Wichita, KansasLease Name Franz Well No. 1Location C SE SW Sec. 30 Twp. 22 Rge. 3 (E) (W) XCounty Harvey Total Depth 620'Abandoned Oil Well Gas Well Input Well SWD Well X D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling Co.Address: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 3 PM Day 3 Month December Year 1964

The Above well was plugged as follows:

5½" plug pushed to 490'. Hole filled with sand to 480' and hole cemented
with 5 sacks. Hole filled with mud to 340'. Rock bridge set from 340'
to 330' and hole cemented with 20 sacks. Hole filled with mud to 40'.
Rock bridge set from 40' to 30' and hole cemented to base of cellar
with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging SupervisorDATE 12-8-64INV. NO. 611-E