

15-079-19162-0000

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasJAN 9 1964
1-9-64
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Drillers Prudction Co.Complete Address: 1020 Union Nat'l. Bldg, Wichita, KansasLease Name Franz Well No. 1Location Q SE SW Sec. 30 Twp. 22s Rge. 3 (E) (W)County Harvey Total Depth 1979'Abandoned Oil Well Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Lost holePlugging Contractor: Sterling Drilling Co.Address: Box 127, Sterling, Kansas License No. RotaryOperation Completed: Hour 2:PM Day 6 Month 1 Year 64

The Above well was plugged as follows:

Squeezed hole w/ 150' sax cement filled hole w/ gravel back to 400'. Set a 1/2 sak hulls
a halco plug and 100' of gravel back to 300' set a 1/2 sak hulls a halco plug and 25' sax
cement. Let it set overnight. Top of plug was 265'. Ran 20 sax cement back to 200'
Filled hole w/ mud from 200' back to 35' set a 5' bridge and ran 8 sax cement from 25' back to z
ero. 4' below ground level. 8 5/8" surface pipe 4' below ground level.
Filled rat hole w/ mud and 2 sax cement 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICEDSigned: [Signature]
Well Plugging SupervisorDATE 1-10-64INV. NO. 8832-E