

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

8-31-70
RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Drillers Production Co. Inc.
Complete Address 480 Fourth Natl. Bk. Bldg. Wichita, Kansas 67202
Lease Name Franz Well No. 1-A
Location W OF C SE SW Sec. 30 Twp. 22 Rge. 3 / (E) (W)
County Harvey Total Depth 3335'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas License No. # 624
Operation Completed: Hour 11 AM Day 29 Month 8 Year 70

The above well was plugged as follows:

13 3/8"-352'-Circulated w/cement. 5 1/2"-3334'-Cemented. Perf. 3306'.
Sand hole to 3300'. 5 Sax. cement 3300' to 3260'. Mud 3260' to 370'.
Bridge 370' to 360'. 35 Sax. cement 360' to 300'. Mud 300' to 40'.
Bridge 40' to 30'. 15 Sax. cement 30' to 0.
Pulled 2193'-5 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8-31-70
WELL NO. 1970-E