

KANSAS

24
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

6-26-72
RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Texaco Inc.

Complete Address Box 2420, Tulsa, Oklahoma 74102

Lease Name E.P. Ward Well No. 5

Location SW SW Sec. 16 Twp. 22 Rge. 33 ~~(E)~~ (W)

County Finney Total Depth 4847'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Gayle E. Toland

Address Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 6:00Pm Day 21 Month 6 Year 1972

The above well was plugged as follows:

8 5/8" to 457' circulated w/ cement. 4 1/2" to 4846' cemented.

Top perforations 4734' Plug bottom w/ 29 sacks cement.

Top of cement 4500' Mud 4500' to 2260'

Spotted 25 sacks cement 2260' to 2180' Mud 2180' to 457'

Spotted 35 sacks cement 457' to 357' Mud 357' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Halliburton Pump Truck

Pulled 2285' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward Eves*
Well Plugging Supervisor

INVOICED

DATE 6/29/72

INV. NO. 5938-W