

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1968
CONSERVATION DIVISION
Wichita, Kansas
12-9-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Texaco Inc.
Complete Address: 614 Bitting Bldg., Wichita, Kns.
Lease Name E.P. Ward Well No. 2
Location G NW SE Sec. 16 Twp. 22 Rge. 33 (E) (W)
County Finney Total Depth 4860'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: None
Plugging Contractor: Russ Casing Pulling Co.
Address: Great Bend, Kansas License No. 623
Operation Completed: Hour 7:00PM Day 6 Month 12 Year 1968

The Above well was plugged as follows:

8 5/8" to 405' circulated w/ cement. 4 1/2" to 4850' cemented.
Top perforations 4690' Plug bottom w/ sand & 4 sacks cement.
Top of cement 4640' Mud 4640' to 375'
~~Spotted~~ Bridge & 30 sacks cement 375' to 275' Mud 275' to 40'
Bridge & 10 sacks cement 40' to 0'.
Pulled 1400' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/9/68
INV. NO. 8963-41

Signed: Edgar J. Eder
Well Plugging Supervisor