

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

12-9-68

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas 67202

Lease Name E.P. Ward Well No. 3

Location C NW SW Sec. 16 Twp. 22 Rge. 33 (E) (W)

County Finney Total Depth 4850'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Russ Casing Pulling co.

Address: Great Bend, Kansas License No. 623

Operation Completed: Hour 5:30Pm Day 4 Month 12 Year 1968

The Above well was plugged as follows:

8 5/8" to 413' circulated w/ cement. 5 1/2" to 4850' cemented.

Top perforations 4712' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4650' Mud 4650' to 410'

Rock bridge & 30 sacks cement 410' to 310' Mud 310' to 40'

Rock bridge & 10 sacks cement 40' to 0'.

Pulled 1693' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Lives
Well Plugging Supervisor

INVOICED

DATE 12/9/68

INV. NO. 8962-11