

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 21, 1967.

RECEIVED
SEP 29 1967
9-29-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name Luders "B" Well No. # 4

Location SE SE SW Sec. 7 Twp. 27 Rge. 12 (E) (W) W

County Pratt Total Depth 4283'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 9:30AM Day 28th Month Sept. Year 1967

The Above well was plugged as follows:

449' of 8 5/8" surface pipe, cemented with 200 sacks. 4283' of 5 1/2" long string, cemented with 200 sacks. Plug back T.D. 4195'. Top perforation 4154'. Bottom of the hole was sanded to 4100', and cemented with 20 sacks, through the dump bailer, with cement from 4100' to 3940'. 2979' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 300', bridge plug and rock bridge from 300' to 290'. 6 sacks of cement was mixed in a barrel, and put on plug at 290', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 19 sacks of cement was added to the plug, with cement from 290' to 215'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/29/67
INV. NO. 6414-W