

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 672177-10-72
RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Co.
Complete Address 1860 Lincoln St Denver, CO
Lease Name Church A Well No. 1
Location SW/SE/NE Sec. 7 Twp. 27 Rge. 12 (E) (W) W
County Pratt Total Depth 4285
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Co. Inc.
Address Box 364 Great Bend, Ks License No. 399
Operation Completed: Hour 10:00 AM Day 8 Month 7 Year 1972

The above well was plugged as follows:

437 ft 8 5/8 surface pipe cemented with 200 sacks. 4228 ft 5 1/2 long
string cemented with 200 sacks. Open hole. Sand back to 4200 ft,
5 sacks cement with bailer. Pulled 2000 ft 5 1/2. Set 25 ft rock bridge
at 325 ft. Fill hole with 8 1/2 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 7-10-72
INV. NO. 6009-W