

15-009-01025-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Barton SEC. 33 TWP. 16 RGE. 11 ~~NE~~/W
 Location as in quarters or footage from lines:
SE/SW/SE

Lease Owner Santa Fe Pipe & Supply
 Lease Name Harzmann Well No. #3
 Office Address Box 562 - Great Bend, Ks. 6753-
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced October 1, 1982
 Plugging completed October 4, 1982
 Reason for abandonment of well or producing formation _____
Depelted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gib Scheck
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3358'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10 3/4"	310'	NONE
				7"	3356'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Halliburton pumped twenty-five (25) sacks 50/50 pozmix cement with
 4% added gel and 3% calcium chloride down the 10 3/4" casing at 400
 psi. Pumped four (4) sacks hulls, fifty (50) sacks cement, fifteen (15)
 sacks gel, seventy (70) sacks cement and one (1) sack hulls down the
 7" casing. Released the plug and pumped seventy (70) sacks cement down
 the 7" casing at 600 psi.
 Capped well with one (1) sack common cement to 5' below the surface.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend,
 (Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of Nov., 1982

My Commission expires: 

Margaret Prosser
 Notary Public.


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. SINCLAIR-PRAIRIE OIL CO.
Farm. Hargman No. 3.

16
SEC. 33 T. 16 R. 11 W
SE SW SE
330' FSL 330' FSL W/2 SE 1/2

Total Depth. 3358
Comm. 3-14-46 Comp. 4-1-46
Shot or Treated.
Contractor. Harbor Drlg.
Issued. 6-22-46

County. Barton
KANSAS



Elevation. 1894

Production. Est. 25 B

CASING:

10 3/4" 310'
7" 3356'

Figures Indicate Bottom of Formations.

surface soils 60
sand 120
shale 200
sand 260
shale & shells 550
red bed 625
shale red 725
anhydrite 750
shale & shells 1170
salt 1330
shale & shells 1430
lime & shale 1450
lime 1565
lime brkn 1650
lime 1720
lime & shale 1805
lime 1885
lime cherty 1890
lime 2040
lime & shale 2060
lime 2195
lime & shale 2370
shale 2400
lime & shale 2575
lime brkn 2600
lime sdy 2620
lime brkn 2670
lime & shale 2740
lime 3015
shale-lime-brkn 3035
lime & shale 3060
lime 3130
lime cherty 3150
lime 3310
lime-conglomerate 3358
Total Depth

Bottom collar - ground level 6' 0
Ground Level - Derrick Floor 2'
Derrick Floor - Top Rotary Bushing 2'

K. G. S. LIBRARY

Tops:	Rig	Surface
Lansing K.C.	3063	3061
Conglomerate	3326	3324
Arbuokle & 7"	3356	3354
Total Depth	3358	3356

2968-80 thin oil stain, no odor
3048 top brown lime
3063 top Lan-K.C.
sli porosity - no show:
3073-78; 3093-09;
3063-67; 3173-82.
3233-38 sli stain & odor.
slight porosity
3243-45 sli. porosity,
sli stain, strong odor.
3258-63 sli porosity, sli.
stain, no odor
3308-13 sli por., sli stain,
no odor

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1982

CONSERVATION DIVISION
Wichita, Kansas

SEP 6 1982