


All Information Completely
Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-009-15120-0000
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County, Sec. 33 Twp. 16S Rge. 11W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NE NW
Lease Owner Shell Oil Company
Lease Name V. O. Harzman Well No. 3
Office Address c/o E. L. Beardon Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed May 15, 1963 19____
Application for plugging approved May 16, 1963 19____
Plugging commenced May 21, 1963 19____
Plugging completed May 23, 1963 19____
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Truman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3360 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	342	none
				4 1/2	3354	609

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved on, broke out cement and cleaned out cellar. Rigged up and worked pipe and measured bridge @ 610'. Hung line and worked line loose.

Worked pipe and shot @ 610'. Pulled 1 jt. and measured in stop @ 582'.

Pumped in 50 sx. cement @ 582' and pulled 250'. Mixed and pumped 10 sx. mud and 50 sx. cement @ 350'. Pulled 280' pipe and pumped in 25 sx. cement to top of surface.

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1963
6-3-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 24th day of May, 1963

Carolyn Herrewé
Notary Public.

My commission expires July 23, 1966

WELL LOG

Shell Oil Company
V. O. Harzman No. 3
SW NE NW Section 33-16S-11W
Kraft-Prusa Field
Barton County, Kansas

Contractor: Company Portable Drilling Unit No. 7
Spud Date: June 16, 1941

FORMATIONS

0	20	Clay
20	355	Sand & Shale
355	555	Sand, Shale & Lime
555	585	Red Bed
585	790	Shale & Anhydrite
790	1820	Shale & Lime
1820	1875	Shale & Chert Streaks
1875	2615	Lime & Shale
2615	2634	Lime & Chert
2634	2714	Shale & Lime
2714	3350	Lime
3350	3360	Dolomite
	3360	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1963
CONSERVATION DIVISION
Wichita, Kansas

CASING RECORD

8 5/8", 32#, SH casing set at 342 feet with 115 sacks cement.
4 1/2", 9.5#, new casing set at 3354 feet with 100 sacks cement.