


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Easting Building  
Wichita, Kansas

Stafford County, Sec. 1 Twp. 22 Rge. (E) 13(W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines SW NE NW  
Lease Owner Fred B. Anschutz  
Lease Name Weiszbrod Well No. 4  
Office Address 1019 Central Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 6-26-1953  
Application for plugging filed 5-17-1956  
Application for plugging approved 5-18-1956  
Plugging commenced 6-8-1956  
Plugging completed 6-14-1956  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 5-1-1956  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation Arbuckle Depth to top 3680 Bottom 3690 Total Depth of Well 3690 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	oil	3668	3686	5-1/2"	3688	3107'
				8-5/8"	250	all

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3692' - 3675' - sand bridge  
3675' - 3650' - 5 sack cement  
3650' - 240' - mud  
240' - 230' - rock mud  
230' - 170' - 20 sack cement  
170' - 35' - mud  
35' - cellar - 10 sack cement

CONSERVATION DIVISION  
Wichita, Kansas

6-29-56

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & S Pipe Pulling Co.  
Address Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Agent  
John W. Ritchey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John W. Ritchey  
1019 Central Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of June, 19 56

My commission expires April 23, 1958

Marc C. Murphy  
Notary Public.

PLUGGING  
FILE SEC. 1 T. 22 R. 13W  
BOOK PAGE 62 LINE 21


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO.  
Farm- Weiszbrod No. 4

SEC. 1 T. 22 R. 13W  
SW NE NW

Total Depth. 3690'  
Comm. 5-16-53 Comp. 5-26-53  
Shot or Treated.  
Contractor.  
Issued. 3-31-56

County Stafford  
KANSAS



Elevation. 1876'

Production. 35 BO & 39% WTR.

CASING:  
8 5/8" 251' cem w/225' sx  
5" 3688'

Figures indicate Bottom of Formations.

sand	230
red bed	255
red bed, shale & shells	695
anhydrite	715
shale	815
shale & shells	1230
salt & shale	1345
shale & shells	1550
lime	1695
sandy lime	1840
lime & shale	2020
lime	2060
lime & shale	2480
shale & shells	2680
lime & shale	2820
lime	3570
shale, lime & chert	3600
lime & chert	3640
lime	3665
shale, chert & lime	3675
lime	3690 RTD
Total Depth	

Tops:

Heebner	3173
Brown Lime	3306
Lansing	3322
Base Kansas City	3545
Conglomerate	3570
Viola	3584
Simpson	3620
Arbuckle	3678

RECEIVED  
STATE GEOLOGICAL SURVEY  
MAY 1 1956  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 1 T. 22 R. 13W  
BOOK PAGE 62 LINE 21