


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Bitting Building
Wichita, Kansas

Stafford County, Sec. 1 Twp. 22S Rge. (E) 13 (W)

Location as "NE/CNW&SW" or footage from lines SE SE SW
Lease Owner Musgrove Petroleum Corporation
Lease Name LOVE Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed January 26, 19 54
Application for plugging filed verbally, January 26, 19 54
Application for plugging approved written, January 28, 19 54
Plugging commenced January 26, 19 54
Plugging completed January 26, 19 54
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes- verbally

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas.
Producing formation Depth to top Bottom Total Depth of Well 3740' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	268'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Loaded hole with mud to 260'. Set first plug with 1/3 sack hulls and 20 sacks cement. Loaded hole with mud to 40'. Set second plug with 1/3 sack hulls and 10 sacks cement.

1-30-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation,
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, GRODON L. KOELLING, (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of January 19 54
Notary Public.

My commission expires September 24, 1956.

PLUGGING
FILE SEC 1 T 22 R 13W
BOOK PAGE 10 LINE 27

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	#1 LOVE
LOCATION:	SE SE SW, Sec. 1-22S-13W Stafford County, Kansas.
COMMENCED:	January 17, 1954
COMPLETED:	January 26, 1954

0	230	Sand & shale
230	268	Red bed
268	400	Red Rock
400	700	Red bed & sand
700	730	Anhydrite
730	1250	Shale
1250	1640	Shale & shells
1640	1775	Shale & lime shells
1775	1845	Lime & shale
1845	1900	Shale & shells
1900	2325	Lime & shale
2325	2420	Shale & shells
2420	2595	Shale & lime shells
2595	2760	Shale & lime streaks
2760	2790	Lime & shale breaks
2790	2830	Shale & lime
2830	2895	Lime & shale breaks
2895	3389	Lime & shale
3389	3530	Lime
3550	3575	Lime & shale
3575	3630	Lime
3630	3655	Lime, chert & shale
3655	3707	Shale & lime
3707	3740	Arbuckle lime
	3740	Rotary Total Depth

Set 8-5/8" surface pipe at 268' with 250 sacks cement.

Dry and Abandoned.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 LOVE, SE SE SW Section 1-22S-13W, Stafford County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By *Gordon L. Koelling*
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 29th day of January, 1954.

REC
STATE OF KANSAS

Melba L. Stumpe

My commission expires September 24, 1956.

PLUGGING
FILE SEC. 1 T 22S 13W
BOOK PAGE 10 LINE 27