


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

WELL PLUGGING RECORD  
OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
off formations.

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 1 Twp. 22 Rge. (E) 13 (W)  
Location as "NE1/4NW1/4SW1/4" or footage from lines SWc NE1/4  
Lease Owner D. R. Lauck  
Lease Name Weiszbrod Well No. 1  
Office Address Wichita Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole  
Date, well completed Nov. 17 1948  
Application for plugging filed Nov. 22 1948  
Application for plugging approved Nov. 22 1948  
Plugging Commenced Nov. 22 1948  
Plugging Completed Dec. 1 1948  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 193...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Stough  
Producing formation none Depth to top Bottom Total Depth of Well 3827 Feet.  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	water	3698	3827	10"	251	none
				5"	3698	2164

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

mud & rock	3827 - 3690
cement	3680 - 3640
mud	3640 - 245
Bridge	245 - 240
cement	240 - 200
mud	200 - 30
bridge	30 - 26
cement	26 - 6 to bottom of cellar

12-11-48

RECEIVED  
Cons. Div.

DEC 11 1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to D. R. Lauck  
Address Wichita, Kans.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
P. R. Bishop (employee of owner)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *P. R. Bishop*

Wichita, Kans. (Address)

SUBSCRIBED AND SWORN to before me this 10 day of December, 1948

My commission expires Sept. 14, 1951

*Elizabeth Gray*  
Notary Public

PLUGGING  
FILE SEC 1 T 22 R 13 W  
BOOK PAGE 22 LINE

D.R.LAUCK

No.1 Weiszbrod

Sec. 1 Twp.22S. R 13W  
SWc NE $\frac{1}{4}$   
Stafford County Kansas

Commenced Oct. 15, 1948

Completed Nov.17, 1948

Casing:

10" 2518 cemented 250 sacks  
5" 3698 cemented 75 "

shale & shells	247
red rock & shale	690
Anhydrite	710
red rock & shells	1090
salt	1260
shale & shells	1575
broken lime	1850
shale & shells	2080
lime & shale	2910
shale & shells	2957
lime & shale	2985
lime	3125
lime & shale	3185
lime	3300
lime & shale	3320
lime	3650
lime & shale	3707
Standardized	
lime	3708
shot 10 qts	3704-3708
Acidized 500 gallons	
lime	3735
lime	3750
show water	
lime	3820
lime	3824
2 $\frac{1}{2}$ B W	
lime	3827

Tops Derrick floor

Heebner	3188
Brown lime	3318
white lime	3336
chert	3599
Simpson	3645
Arbuckle	3698
Rotary T.D.	3705

HFW

D & A

**PLUGGING**  
FILE SEC. 1 T22 R13W  
BOOK PAGE 78 LINE 7

**RECEIVED**  
DEC 11 1948  
STATION  
COMMISSION  
KANSAS