

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.10890-0000

API NUMBER NONE

LEASE NAME Weiszbrod

WELL NUMBER 1

SPOT LOCATION NW NE NW

SEC. 1 TWP. 22 RGE. 13 (E) or (W) (W)

COUNTY Stafford

Date Well Completed 2/22/53

Plugging Commenced 6/22/85

Plugging Completed 7/03/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well Inj.
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. 1 - Dodge City (J.H. Metz on location)

Is ACO-1 filed? N/A if not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3669' bottom 3718' T.D. 3718'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & Water	3669	72	8 5/8	244	NONE
KC	Oil & Water	3318	3530	5 1/2	3671	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Spot cement @ 2470' to 1673'. Spotted gel & mud to 961'. Spotted cement from 961' to surface. Pumped 100 sax between 8 5/8" & 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address Box 723, Hays, KS 67601


STATE OF Kansas COUNTY OF Sedgwick, ss.

Melvyn D. Abels (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

*Rec'd
7-11-85*

(Signature) Mel Abels

(Address) 970 4th Fin. Ctr, Wichita, KS



*Rec'd
7-19-85
KCC*

SUBSCRIBED AND SWORN TO before me this 18 day of July, 19 85

Cecelia A. Bowser
Notary Public

My Commission expires: 8/05/87

DRILLER'S LOG

Anschutz Drilling Company, Inc.
 #1 Welszbrod
 NW NE NW - 1-22S-13W
 Stafford County, Kansas

<u>FROM</u>	<u>TO</u>	
0	45	Clay
45	235	Sand
235	248	Red rock
248	500	Red shale
500	700	Red bed
700	735	Anhydrite
735	1230	Shale & shells
1230	1260	Salt
1260	1565	Salt, shale & shells
1565	1725	Lime & shale
1725	1915	Lime
1915	2230	Lime & shale
2230	2400	Shale
2400	2655	Shale & lime
2655	2795	Shale
2795	3005	Lime & shale
3005	3180	Lime
3180	3275	Lime & shale
3275	3555	Lime
3555	3585	Lime, shale & chert
3585	3618	Viola chert
3618	3645	Shale
3645	3672	Shale & lime
	3672	ROTARY TOTAL DEPTH

COMMENCED: 2-10-53

COMPLETED: 2-22-53

CASING RECORD

Set 8-5/8" surface casing at 244'
 with 225 sacks cement.
 Set 5-1/2" casing at 3671' with
 200 sacks cement.

ELEVATION: 1881 RB

TOPS

Anhydrite 700
 Heebner 3174
 Brown Lime 3304
 Lansing 3318 (-1437)
 Viola 3571
 Simpson 3615
 Arbuckle 3669

STATE OF KANSAS

COUNTY OF SEDGWICK

)
) SS
)

I hereby affirm that the above and foregoing is a true and correct copy of the of the #1 Welszbrod located NW NE NW of Section 1-22S-13W, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY

BY:

Leon L. Mehler
 Leon L. Mehler

Subscribed and sworn to before me this 1st day of May, 1953.

Wilma N. Hoffman
 Notary Public

My Commission Expires: May 24, 1956