

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 1 TWP. 22S RGE. 13 NW
Location as in quarters or footage from lines:
NW SE SE

Lease Owner N - B Company, Inc.
 Lease Name Drach Well No. 1
 Office Address P.O. Box 506, Russell, KS 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 2-15-82
 Application for plugging filed 2-15-82
 Plugging commenced 2-15-82
 Plugging completed 2-15-82
 Reason for abandonment of well or producing formation
Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3709'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	314'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud laden fluid @ 3709' - 600'
 60 sks cement @ 600'
 40 sks cement @ 300'
 10 sks cement @ 40'
 10 sks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1982
2-26-82
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.
Joe K. Branum (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
P.O. Box 506, Russell, KS 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of February, 19 82

Joyce Ann Ridgley
Notary Public.

My Commission expires: April 29, 1984.



EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665

DRILLERS LOG

OPERATOR: N - B Company, Inc.
P. O. Box 506
Russell, Kansas 67665

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665

LEASE: Drach WELL: #1

LOCATION: NW SE SE
Section 1-22S-13W
Stafford County, Kansas

Total Depth: 3709'

Elevation: 1883' K.B.

Commenced: 2-4-82

Completed: 2-15-82

Casing: 8-5/8" @ 314' with 275 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top soil & sand	30'	Shale	1750'
Sand & shale	700'	Shale & lime (R.T.D.)	3709'
Anhydrite	722'		

STATE OF KANSAS)

SS:


COUNTY OF RUSSELL)


I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned well.


Joe K. Branum

Subscribed and sworn to before me this 22nd day of February, 1982.

My Commission Expires: April 29, 1984.




Notary Public