

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 1 TWP. 22S RGE. 13W E/W
Location as in quarters or footage from lines:
C of N/2 NE SW

Lease Owner Okmar Oil Co.
Lease Name Love #1 Well No. _____
Office Address RK P.O. Box 723, Hays, Ks. 67601
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4/8/81
Plugging completed 4/10/81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ~~XXXXXXXX~~ Maurice Leslie

Producing formation _____ Depth to top _____ bottom _____ T.D. 3703

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	232	None
				5-1/2	3692	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeezed 5 1/2" casing with 2 sacks hulls and 10 sacks gel. Released plug and displaced with 75 sacks cement. Between 8-5/8" and 5 1/2" casing, squeezed with 3 sacks hulls, 10 sacks gel and 125 sacks cement. Cut off bradenhead. Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION

4-14-81

APR 14 1981

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING CONSERVATION DIVISION
CHASE, KANSAS Wichita Kansas

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1981

My Commission expires



Joan Kelso
Notary Public.

W E L L L O G
 Love # 1
 Center, N/2 NE SW 1-22-13
 Stafford County, Kansas

0	200	Clay and sand	Elevation	1885' K.B.
200	1580	Red bed and shale		
1580	2170	Lime	<u>Formation Tops:</u>	
2170	2945	Shale and lime		
2945	3064	Lime	Heebner	3182'
3064	3340	Lime and shale	Brown lime	3311
3340	3570	Lime	Kansas City	3229
3570	3631	Lime - chert - shale	Base K. C.	3545
3631	3670	Chert & shale	Conglomerate	3581
3670	3703	Shale and lime	Viola	3598
3703		T. D.	Simpson	3628
			Arbuckle-shaley	3684
			Arbuckle	3689
			T. D.	3703

STATE OF KANSAS

COUNTY OF BARTON ss

T. D. Sweetman, partner of S & S Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

T. D. Sweetman

Subscribed and sworn before me this 25th day of May, 1961.

Dean Kember
 Notary Public Barton County

My Commission expires December 3, 1963.

MAY 25 1961
 BARTON COUNTY, KANSAS