


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 1 Twp. 22S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines CW/2 NW NE
Lease Owner M & L Oil Company
Lease Name Weizbrod Well No. 1
Office Address 913 Brown Bldg. - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed September 10 19 54
Application for plugging approved September 13 19 54
Plugging commenced September 15 19 54
Plugging completed September 20 19 54
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3692 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	267'	None
				5-1/2"	3678'	2898'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3692' to 3670'
and ran 5 sacks of cement. Mudded and
bailed hole to 250', set a 10' rock bridge
and ran 20 sacks of cement. Mudded hole to
35', and ran 10 sacks of cement on top.
Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF _____, COUNTY OF _____, ss.
_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address) _____

SUBSCRIBED AND SWORN to before me this 17 day of Sept, 19 54

My commission expires 12-1-56 [Signature] Notary Public.

PLUGGING
FILE SEC 1 T 22 R 13W
BOOK PAGE 63 LINE 11

9-23-54

DRILLERS' LOG

COPY

Weiszbrod #1A
 Commenced R. D.: 1-20-54
 Completed R. D.: 2-1-54
 Total Depth: 3690'
 Casing Record: 267' of 8 5/8"

CW $\frac{1}{2}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$ of Sec. 1-22S-13W
 Stafford County, Kansas
 Elevation: 1877 D. F.
 Initial Prod.: Arbuckle
 Contractor : Buick Drilling Inc.

STRATA	DEPTH
Surface clay and sand	0 - 130
Sand and shale	130 - 215
Shale	215 - 255
Red bed	255 - 267
Red bed, shale, and shells	267 - 660
Anhydrite and shale	660 - 690
Red bed, shale and shells	690 - 1140
Shale and shells	1140 - 1550
Broken lime and shells	1550 - 1660
Shale and lime	1660 - 2835
Shale, lime and shells	2835 - 2940
Lime and shale	2940 - 3475
Lime	3475 - 3530
Lime and shale	3530 - 3545
Cherty lime	3545 - 3610
Chert and shale	3610 - 3635
Shale and lime	3635 - 3680
Lime	3680 - 3690 T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 OCT - 1 1954
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

H. R. Buick, President

Signed and sworn to in my presence this 2nd day of February, 1954, by H. R. Buick, President of the Buick Drilling INC.

Notary Public, Roberta Shogren

My commission expires December 26, 1955.

